BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work : Construction of drain connecting BB nagara to Sonnegowda layout in ward no. 8, kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	30.00	Hire charges of 100 KVA generator including operator, fuel, transportation and handling charges	Hours	630.00	
2	329.62	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH	cum	83.16	
3	12.15	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications.- Rubble stone masonry in cement mortar	cum	250.56	
4	80.10	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5070.60	
5		Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.			
6	8.50	With Available stones	cum	3852.36	
7	147.05	With New stones	cum	5159.16	
8	588.00	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	97.20	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	18.79	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5491.80	
10	282.00	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Approved data rate enclosed)	sqm	1600.00	
11	280.18	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	78.97	

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(ಸೊನ್ನೆ)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

26/12

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

24/12